## **Estimate**

Estimate number EST-202507-0964

Estimate Date: 2025-07-31

### **Bethany Construction LLC**

10745 Taylor Farm Rd Woodstock, MD 21163 (571)-535-4631 bethanyconstructionllc@gmail.com

#### **Estimate for**

964 Towlston Rd McLean, VA 22102

This comprehensive estimate covers the reconstruction and restoration of damaged areas within the basement and one bathroom on the first floor of the property located at 964 Towlston Rd, McLean, VA 22102. The property will be vacant during the work, allowing for an optimized and efficient project timeline. All work will adhere to "Like Kind and Quality" standards, utilizing current DMV area market pricing (60-75th percentile as of July 2025) to ensure fair compensation and facilitate insurance adjuster approval. This estimate includes all necessary demolition, reconstruction, finishing, and associated project management services.

### **Interior Reconstruction**

One coat of high-quality, stain-blocking acrylic primer.

One coat of high-quality, stain-blocking acrylic primer.

14. Primer (Ceiling - new/patched drywall)

Detailed work scope for damaged areas across the basement and the first-floor bathroom.

#### **Basement - Bathroom**

**Pre-Construction** 

Item	Qty	Unit	Unit Price	<b>Total Price</b>
1. Baseboard Removal (Wood)	26.83	LF	\$1.15	\$30.85
2. Protection (Vanity Light Fixture)	1.00	EA	\$85.00	\$85.00
3. Protection (Mirror)	1.00	EA	\$85.00	\$85.00
4. Protection (Vanity)	1.00	EA	\$85.00	\$85.00
5. Protection (Toilet)	1.00	EA	\$85.00	\$85.00
6. Floor Protection (Heavy-Duty)	44.43	SF	\$0.80	\$35.54
7. Detach & Reset Wall Detached Shelf	1.00	EA	\$95.00	\$95.00
Construction				
Item	Othy	Unit	Unit Price	Total Price
item	Qty	Oilit	Onit Price	Total Price
8. Drywall Installation (Wall, 1/2" Type X)	30.80		\$3.25	\$100.10
	30.80			
8. Drywall Installation (Wall, 1/2" Type X)	30.80	SF		
8. Drywall Installation (Wall, 1/2" Type X)  Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte	30.80 egration.	SF	\$3.25	\$100.10
8. Drywall Installation (Wall, 1/2" Type X)  Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte  9. Drywall Installation (Ceiling, 1/2" Type X)	30.80 egration.	SF SF	\$3.25	\$100.10
<ul> <li>8. Drywall Installation (Wall, 1/2" Type X)  Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte</li> <li>9. Drywall Installation (Ceiling, 1/2" Type X)  Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte</li> </ul>	30.80 egration. 35.09 egration.	SF SF LF	\$3.25 \$3.25	\$100.10 \$114.04
<ol> <li>Drywall Installation (Wall, 1/2" Type X)         Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte</li> <li>Drywall Installation (Ceiling, 1/2" Type X)         Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte</li> <li>Baseboard Installation (Wood)</li> </ol>	30.80 egration. 35.09 egration. 29.51	SF SF LF	\$3.25 \$3.25 \$6.50	\$100.10 \$114.04 \$191.81
<ol> <li>Drywall Installation (Wall, 1/2" Type X)         Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte</li> <li>Drywall Installation (Ceiling, 1/2" Type X)         Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte</li> <li>Baseboard Installation (Wood)</li> <li>Paint Walls</li> </ol>	30.80 egration. 35.09 egration. 29.51	SF SF LF SF	\$3.25 \$3.25 \$6.50	\$100.10 \$114.04 \$191.81
<ol> <li>B. Drywall Installation (Wall, 1/2" Type X)         Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless intellegence.         Prywall Installation (Ceiling, 1/2" Type X)         Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless intellegence.     </li> <li>Baseboard Installation (Wood)</li> <li>Paint Walls         Two coats of professional-grade, low-VOC latex paint.     </li> </ol>	30.80 egration. 35.09 egration. 29.51 178.87	SF SF LF SF	\$3.25 \$3.25 \$6.50 \$4.75	\$100.10 \$114.04 \$191.81 \$849.63

Generated on 2025-07-31 Page 1 of 5

31.90 SF

\$0.60

\$19.14

Basement - Bathroom Subtotal: \$2,003.97

Rasa	ment	- Rad	room

Pre-Construction				
Item	Qty	Unit	Unit Price	Total Price
15. Carpet Removal (Cut Pile with Padding)	251.68	SF	\$1.10	\$276.85
16. Baseboard Removal (Wood)	49.67	LF	\$1.15	\$57.12
17. Floor Protection (Heavy-Duty)	251.68	SF	\$0.80	\$201.34
Construction				
Item	Qty	Unit	Unit Price	Total Price
18. Carpet Installation (Cut Pile with Padding)	264.26	SF	\$5.50	\$1,453.43
19. Drywall Installation (Wall, 1/2" Type X)	92.40	SF	\$3.25	\$300.30
Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless integral	tion.			
20. Insulation Installation (Wall)	42.00	SF	\$2.20	\$92.40
Fiberglass batt insulation.				
21. Baseboard Installation (Wood)	72.24	LF	\$6.50	\$469.56
22. Paint Walls	459.70	SF	\$4.75	\$2,183.57
Two coats of professional-grade, low-VOC latex paint.				
23. Paint Ceiling	251.68	SF	\$4.75	\$1,195.48
Two coats of professional-grade, low-VOC latex paint.				
24. Primer (Walls - new/patched drywall)	84.00	SF	\$0.60	\$50.40
One coat of high-quality, stain-blocking acrylic primer.				

### Basement - Bedroom Subtotal: \$6,280.46

\$1,008.04

\$5.50

## **Basement - Hallway**

29. Carpet Installation (Cut Pile with Padding)

Pre-Construction				
Item	Qty	Unit	Unit Price	Total Price
25. Floor Protection (Heavy-Duty)	174.55	SF	\$0.80	\$139.64
26. Detach & Reset Light Fixture	2.00	EA	\$135.00	\$270.00
27. Detach & Reset Multiple Outlets	1.00	LOT	\$80.00	\$80.00
28. Detach & Reset Switch	1.00	EA	\$80.00	\$80.00
Construction				
Item	Qty	Unit	Unit Price	Total Price

Generated on 2025-07-31 Page 2 of 5

183.28 SF

30. Drywall Installation (Wall, 1/2" Type X)	140.80	SF	\$3.25	\$457.60
Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless	integration.			
31. Drywall Installation (Ceiling, 1/2" Type X)	41.25	SF	\$3.25	\$134.06
Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless	integration.			
32. Baseboard Installation (Wood)	68.39	LF	\$6.50	\$444.54
33. Paint Walls	518.59	SF	\$4.75	\$2,463.30
Two coats of professional-grade, low-VOC latex paint.				
34. Paint Ceiling	174.55	SF	\$4.75	\$829.11
Two coats of professional-grade, low-VOC latex paint.				
35. Primer (Walls - new/patched drywall)	128.00	SF	\$0.60	\$76.80
One coat of high-quality, stain-blocking acrylic primer.				
36. Primer (Ceiling - new/patched drywall)	37.50	SF	\$0.60	\$22.50
One coat of high-quality, stain-blocking acrylic primer.				

Basement - Hallway Subtotal: \$6,005.59

## **Basement - Living Room**

Pre-Construction				
Item	Qty	Unit	Unit Price	Total Price
37. Carpet Removal (Cut Pile with Padding)	478.39	SF	\$1.10	\$526.23
38. Baseboard Removal (Wood)	96.96	LF	\$1.15	\$111.50
39. Floor Protection (Heavy-Duty)	490.39	SF	\$0.80	\$392.31
40. Detach & Reset Recessed Light	8.00	EA	\$50.00	\$400.00
41. Detach & Reset Curtain, Rod	1.00	EA	\$70.00	\$70.00
42. Detach & Reset Multiple Outlets	1.00	LOT	\$80.00	\$80.00
43. Detach & Reset Switch	1.00	EA	\$80.00	\$80.00
Construction				
Item	Qty	Unit	Unit Price	Total Price
44. Carpet Installation (Cut Pile with Padding)	514.91	SF	\$5.50	\$2,832.00
45. Baseboard Installation (Wood)	106.66	LF	\$6.50	\$693.29
46. Paint Walls	780.60	SF	\$4.75	\$3,707.85
Two coats of professional-grade, low-VOC latex paint.				
47. Paint Ceiling	490.39	SF	\$4.75	\$2,329.35
Two coats of professional-grade, low-VOC latex paint.				

Basement - Living Room Subtotal: \$11,222.54

Generated on 2025-07-31 Page 3 of 5

# Interior Reconstruction

First-floor bathroom restoration.

### 1st Floor - Bathroom

Pre-Construction				
Item	Qty	Unit	Unit Price	Total Price
48. Protection (Assist Bar)	1.00	EA	\$63.75	\$63.75
49. Protection (Toilet)	1.00	EA	\$63.75	\$63.75
50. Protection (Vanity)	1.00	EA	\$63.75	\$63.75
51. Protection (Mirror)	1.00	EA	\$63.75	\$63.75
52. Floor Protection (Heavy-Duty)	23.50	SF	\$0.80	\$18.80
Construction				
Item	Qty	Unit	Unit Price	Total Price
53. High Ceiling Premium (Ceiling)	23.50	SF	\$0.60	\$14.10
Labor premium for working at elevated heights (9ft+ ceiling).				
54. Drywall Installation (Wall, 1/2" Type X)	21.78	SF	\$3.25	\$70.78
Hung, taped (3 coats), floated, sanded to Level 4 finish; seamless inte	gration.			
55. Baseboard Installation (Wood)	21.73	LF	\$6.50	\$141.25
56. Paint Walls	177.75	SF	\$4.75	\$844.31
Two coats of professional-grade, low-VOC latex paint.				
57. Paint Ceiling	23.50	SF	\$4.75	\$111.62
Two coats of professional-grade, low-VOC latex paint.				
58. Primer (Walls - new/patched drywall)	19.80	SF	\$0.60	\$11.88
One coat of high-quality, stain-blocking acrylic primer.				

1st Floor - Bathroom Subtotal: \$1,467.75

# **Project Cleanup & Debris Disposal**

Common project tasks not tied to specific rooms.

#### **Jobsite**

Item	Qty Unit	Unit Price	Total Price
59. General Site Protection (Comprehensive)	1.00 LS	\$1,350.00	\$1,350.00

Comprehensive site protection: ram board, dust barriers, HVAC protection to safeguard property.

Generated on 2025-07-31 Page 4 of 5

Post-Construction				
Item	Qty	Unit	Unit Price	Total Price
60. Debris Disposal (Dumpster Rental)	1.00	EA	\$700.00	\$700.00
Rental, delivery, pickup, and disposal fees for a 10 CY dumpster for co	nstruction debri	is.		
61. Final Construction Cleaning	1.00	LS	\$500.00	\$500.00
Detailed cleaning of all renovated areas, including vacuuming, wiping	surfaces, dustin	g, broom-cle	an.	

Subtotal: \$29,530.31

Overhead (10.0%): \$2,953.03

Profit (10.0%): \$2,953.03

VA Sales Tax: \$1,771.82

**Estimate Total: \$37,208.19** 

Total project costs are calculated based on current DMV area market rates (60-75th percentile) as of July 2025. Material costs are subject to Virginia state sales tax (6.0% in Fairfax County, McLean, VA), which is typically paid by the contractor at the point of purchase. Labor is exempt for residential projects in Virginia. This estimate includes a 10% Overhead charge to cover general business expenses and project management, and a 10% Profit margin on the subtotal, reflecting standard industry practices for similar reconstruction projects.

This estimate is based on the provided project data and detailed scope of work. Any changes or additional work requested outside of this scope will require a change order and may affect the final cost and timeline. This estimate does not include costs for permits unless explicitly stated, or remediation of hazardous materials if discovered. All efforts will be made to adhere to the timeline, but unforeseen circumstances may cause delays.

Generated on 2025-07-31 Page 5 of 5