# **Estimate**

Estimate number EST-202508-5709

Estimate Date: 2025-08-05

#### JJL Contractor Inc.

6517 Creek Run Dr Centreville, Virginia 20121 571-365-5055 projjlinc@gmail.com

### **Estimate for**

15709 Rothschild Ct Haymarket, VA 20169-6177

Comprehensive interior reconstruction project including drywall repair, complete interior painting, carpet replacement, and restoration services across 6 rooms. Project includes high ceiling work requiring specialized equipment, extensive fixture coordination, and comprehensive site protection for occupied residence. All work performed to current building codes and industry standards.

## **Interior Reconstruction**

Room-by-room reconstruction work including Bedroom (combined main/subroom/bay), Living Room, Kitchen (combined main/bay), Entry/Foyer, Hallway, and Garage. All work performed to current IRC and Virginia building standards.

#### **Bedroom**

343.53 SF floor area, peaked/8' ceiling height. Combined main bedroom, subroom, and bay area with comprehensive flooring replacement.

### **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
1. Floor Protection	343.53	SF	\$0.75	\$257.65
Protective film installation and removal for occupied residence				
2. Detach & Reset Items	5.00	EA	\$85.00	\$425.00
Curtain/window drapery hardware (3 EA), recessed light fixture trim (1	EA), cold air re	turn cover (1	EA)	

### Construction

Item	Qty	Unit	Unit Price	Total Price	
3. Drywall Repair & Integration	192.00	SF	\$4.95	\$950.40	
1/2" drywall installation on walls (96 SF) and ceiling (96 SF), taping, floa	ting, and textu	ıre matching			
4. Primer Application	192.00	SF	\$1.45	\$278.40	
Primer application on all new and repaired drywall surfaces					
5. Wall Painting	758.35	SF	\$2.70	\$2,047.55	
Two-coat paint application on all walls					
6. Ceiling Painting	365.26	SF	\$2.70	\$986.20	
Two-coat paint application on ceiling					
7. Baseboard Removal	87.40	LF	\$2.50	\$218.50	
Careful removal of existing baseboard for carpet installation access					
8. Carpet Removal	343.53	SF	\$1.55	\$532.47	
Complete removal of existing carpet and padding					
9. Carpet Installation	371.00	SF	\$5.15	\$1,910.65	
New carpet installation with padding and stretch-in method (includes 8% waste factor)					
10. Baseboard Reinstallation	87.40	LF	\$4.25	\$371.45	
Reinstall baseboard with new fasteners and caulking					

Generated on 2025-08-05 Page 1 of 6

## 11. Baseboard Touch-up Paint

87.40 LF

\$1.85

\$161.69

Touch-up paint application on reinstalled baseboard

Bedroom Subtotal: \$8,139.96

# **Living Room**

541.93 SF floor area, 18'3" high ceiling requiring specialized scaffolding equipment and safety protocols per OSHA 1926.451

### **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
12. Floor Protection	541.93	SF	\$0.75	\$406.45
Protective film installation and removal for occupied residence				
13. Large Fixture Protection	2.00	EA	\$45.00	\$90.00
Mask and cover large ornate light fixtures during construction				
14. Detach & Reset Items	2.00	EA	\$85.00	\$170.00
Large curtain and window drapery hardware for 2-story height				

## Construction

Item	Qty	Unit	Unit Price	Total Price
15. Drywall Repair & Integration	32.00	SF	\$4.95	\$158.40
1/2" drywall installation on ceiling (32 SF), taping, floating, and texture many	atching			
16. Primer Application	32.00	SF	\$1.45	\$46.40
Primer application on all new and repaired drywall surfaces				
17. High Wall Painting	1,659.00	SF	\$3.85	\$6,387.15
Wall painting for 18'3" height using scaffolding and safety equipment				
18. High Ceiling Painting	541.93	SF	\$3.85	\$2,086.43
Ceiling painting for 18'3" height using scaffolding and safety equipment				
19. Height Premium Labor	541.93	SF	\$0.75	\$406.45
Additional labor costs for elevated work and safety measures				

Living Room Subtotal: \$9,751.28

### Kitchen

289.74 SF floor area, 8' ceiling height. Combined main kitchen and bay area with careful attention to fixture protection.

# **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
20. Floor Protection	289.74	SF	\$0.75	\$217.31
Protective film installation and removal for occupied residence				
21. Large Fixture Protection	1.00	EA	\$45.00	\$45.00
Mask and cover large light fixture during construction				

Generated on 2025-08-05 Page 2 of 6

# 22. Detach & Reset Items 7.00 EA \$85.00 \$595.00

Recessed light trim (6 EA) and window drapery hardware (1 EA)

Construction				
Item	Qty	Unit	Unit Price	Total Price
23. Drywall Repair & Integration	24.00	SF	\$4.95	\$118.80
1/2" drywall installation on walls (12 SF) and ceiling (12 SF), taping, float	ing, and textu	ıre matching		

24. Primer Application 24.00 SF \$1.45 \$34.80

Primer application on all new and repaired drywall surfaces

25. Wall Painting
451.31 SF \$2.70 \$1,218.54

Two-coat paint application on walls

26. Ceiling Painting 289.74 SF \$2.70 \$782.30

Two-coat paint application on ceiling

Kitchen Subtotal: \$3,011.74

# **Entry/Foyer**

99.83 SF floor area, 18'3" high ceiling requiring specialized scaffolding equipment and safety protocols per OSHA 1926.451

### **Pre-Construction**

Item	Qty	Unit	Unit Price	<b>Total Price</b>
27. Floor Protection	99.83	SF	\$0.75	\$74.87
Protective film installation and removal for occupied residence				
28. Large Fixture Protection	1.00	EA	\$45.00	\$45.00
Mask and cover large ornate light fixture during construction				

### Construction

Item	Qty	Unit	Unit Price	Total Price
29. High Wall Painting	610.88	SF	\$3.85	\$2,351.89
Wall painting for 18'3" height using scaffolding and safety equipment				
30. High Ceiling Painting	99.83	SF	\$3.85	\$384.35
Ceiling painting for 18'3" height using scaffolding and safety equipment				
31. Height Premium Labor	99.83	SF	\$0.75	\$74.87
Additional labor costs for elevated work and safety measures				

Entry/Foyer Subtotal: \$2,930.98

# Hallway

431.33 SF floor area, 8' ceiling height with extensive fixture coordination requirements

Generated on 2025-08-05 Page 3 of 6

Pre-Construction				
Item	Qty	Unit	Unit Price	Total Price
32. Floor Protection	431.33	SF	\$0.75	\$323.50
Protective film installation and removal for occupied residence				
33. Large Fixture Protection	1.00	EA	\$45.00	\$45.00
Mask and cover large ornate light fixture during construction				
34. Detach & Reset Items	15.00	EA	\$85.00	\$1,275.00
Recessed light fixture trim (6 EA), Heat/AC registers (4 EA), cold air hardware (1 EA)	return covers (2 E	EA), smoke a	letectors (2 EA), curta	ain/window

ltem	Qty	Unit	Unit Price	Total Price
35. Wall Painting	641.86	SF	\$2.70	\$1,733.02
Two-coat paint application on walls				
36. Ceiling Painting	431.33	SF	\$2.70	\$1,164.59
Two-coat paint application on ceiling				

37. Carpet Deep Cleaning & Deodorizing 431.33 SF \$1.25 \$539.16

Qty Unit

Deep cleaning and deodorizing service for existing carpet including stain treatment and odor elimination

Hallway Subtotal: \$5,080.27

**Total Price** 

**Unit Price** 

## Garage

Item

429.02 SF floor area, 8' ceiling height. 2-car garage with special attention to garage door hardware and opener units.

### **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
38. Floor Protection	429.02	SF	\$0.75	\$321.76

Protective film installation and removal for occupied residence

## Construction

Item	Qty	Unit	Unit Price	Total Price
39. Drywall Repair & Integration	48.00	SF	\$4.95	\$237.60
1/2" drywall installation on ceiling (48 SF), taping, floating, and texture mat	ching			
40. Primer Application	48.00	SF	\$1.45	\$69.60
Primer application on all new and repaired drywall surfaces				
41. Wall Painting	576.00	SF	\$2.70	\$1,555.20

Two-coat paint application on walls, careful work around garage door supports

Generated on 2025-08-05 Page 4 of 6

42. Ceiling Painting 429.02 SF \$2.70 \$1,158.35

Two-coat paint application on ceiling

Garage Subtotal: \$3,342.52

# **Project Management & Site Services**

Comprehensive project coordination, protection services, and cleanup management for occupied residence

### **Project Common Items**

Project-wide services including coordination, protection, cleanup, and debris management

### **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
43. Material Delivery Coordination	1.00	LS	\$150.00	\$150.00
Scheduled delivery management to minimize disruption in occupied ho	me			
44. Daily Construction Cleanup	12.00	DAY	\$20.00	\$240.00
Ongoing site maintenance and safety protocols for occupied residence	including dust	control per O	SHA 1910.1000	
45. Scaffold Rental & Setup	1.00	LS	\$275.00	\$275.00
Professional scaffolding rental and setup for high-ceiling work (18'3") c	ompliant with C	SHA 1926.45	51 standards	

## **Post-Construction**

Item	Qty Unit	Unit Price	Total Price
46. Construction Debris Disposal	1.00 LS	\$870.00	\$870.00
Waste management including 10-yard dumpster rental, material segreg yards total waste	ation, and proper dispos	al at authorized facilities	for 4.5 cubic
47. Final Construction Cleaning	1.00 LS	\$355.00	\$355.00
Post-construction cleaning including detailed dust removal, surface prepared	paration, and final prepai	ration	

Project Common Items Subtotal: \$1,890.00

Subtotal: \$34,146.75

Overhead (17.0%): \$5,804.95

VA Sales Tax: \$457.43

**Estimate Total: \$40,409.13** 

**Overhead & Profit:** 17% applied to cover project management, supervision, quality control, and coordination of multiple trades including drywall, painting, flooring, and fixture work.

**Sales Tax:** Virginia rate of 6.0% applied to materials only; labor is tax-exempt for residential construction per Virginia state tax code.

Generated on 2025-08-05 Page 5 of 6

15709 Rothschild Ct Haymarket, VA, 20169-6177

**Scope of Work:** This estimate covers comprehensive interior reconstruction including drywall repair, interior painting, carpet replacement, and all associated restoration services. All materials will meet "like kind and quality" standards.

Warranty: 2-year workmanship warranty on all installation and repair work.

Timeline: Project estimated at 12-18 business days depending on material delivery and drying times.

**Terms:** Estimate valid for 30 days. Additional work beyond this scope will require separate pricing. Payment terms available upon contract execution.

Generated on 2025-08-05 Page 6 of 6