# **Estimate**

Estimate number EST-202508-5652

Estimate Date: 2025-08-05

#### **JJL Contractor Inc.**

6517 Creek Run Dr Centreville, Virginia 20121 (571) 365-5055 jjpro715@outlook.com

### **Estimate for**

5652 5th Street North Arlington, VA 22205

Interior residential reconstruction project involving comprehensive water damage repair across four rooms totaling 450.27 SF on the first floor. This estimate details interior reconstruction following a residential loss, including carpet replacement, drywall patching, complete baseboard and quarter round replacement, and comprehensive painting throughout occupied property. All work performed in accordance with IRC 2018, Arlington County building codes, and local building codes (IRC), with costs based on current DMV market rates as of August 2025. Project requires specialized contents manipulation and coordination due to occupied property status, aligning with IRC Section R702 for interior finishes and VA USBC for code compliance.

# Interior Reconstruction

Room-by-room reconstruction including Bedroom 1, Bedroom 2, Hallway, and Living Room with specialized work requirements. Scope includes demolition, patching, installation, and finishing for all surfaces across four rooms on the first floor.

### **Bedroom 1**

92.01 SF room with curtain rod detach/reset required. Height: 8 ft, wall area: 308 sq ft, floor area: 92.01 sq ft, perimeter: 38.5 lf.

#### **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
Remove existing carpet	77.01	SF	\$0.85	\$65.46
Carpet and pad removal including disposal preparation				
2. Remove existing baseboard	38.50	LF	\$1.50	\$57.75
Careful removal to prevent wall damage				
3. Remove existing quarter round	38.50	LF	\$1.25	\$48.12
Trim removal with wall protection				
4. Detach/reset curtain rod	1.00	EA	\$45.00	\$45.00
Temporary removal and reinstallation				

#### Construction

Item	Qty	Unit	Unit Price	Total Price
5. Drywall patch and integration	15.40	SF	\$4.25	\$65.45
1/2" Type X gypsum board with feathered edges extending 6" beyond patch	area for s	eamless tra	ansition per IRC R702	
6. Carpet and pad installation	92.01	SF	\$6.50	\$598.07
Professional installation with seaming as required				
7. Tackless strip installation	38.50	LF	\$2.25	\$86.62
Perimeter installation per manufacturer specifications				
8. Baseboard installation	38.50	LF	\$8.75	\$336.88
Like kind and quality replacement with proper fastening				
9. Quarter round installation	38.50	LF	\$5.50	\$211.75

Page 1 of 6

Generated on 2025-08-05

Finish trim installation with mitered corners

JJL Contractor Inc. 6517 Creek Run Dr Centreville, Virginia, 20121 (571) 365-5055 jjpro715@outlook.com

10. Primer application	15.40	SF	\$1.25	\$19.25
High-quality primer for patch areas				
11. Wall paint application (2 coats)	308.00	SF	\$2.65	\$816.20
Premium latex paint with even coverage				
12. Baseboard and quarter round paint	77.00	LF	\$2.25	\$173.25
Trim painting with cut-in technique				

Bedroom 1 Subtotal: \$2,523.80

### Bedroom 2

134.33 SF room with curtain and window blind detach/reset required. Height: 8 ft, wall area: 386.67 sq ft, floor area: 134.33 sq ft, perimeter: 48.33 lf.

Pre-Construction				
Item	Qty	Unit	Unit Price	Total Price
13. Remove existing carpet	120.33	SF	\$0.85	\$102.28
Carpet and pad removal including disposal preparation				
14. Remove existing baseboard	48.33	LF	\$1.50	\$72.50
Careful removal to prevent wall damage				
15. Remove existing quarter round	48.33	LF	\$1.25	\$60.41
Trim removal with wall protection				
16. Detach/reset curtain	1.00	EA	\$35.00	\$35.00
Temporary removal and reinstallation				
17. Detach/reset window blind	1.00	EA	\$35.00	\$35.00
Careful handling and reinstallation				

Construction				
Item	Qty	Unit	Unit Price	Total Price
18. Drywall patch and integration	30.80	SF	\$4.25	\$130.90
1/2" Type X gypsum board with feathered edges extending 6" beyond pa	tch area for s	eamless tr	ansition per IRC R702	
19. Carpet and pad installation	134.33	SF	\$6.50	\$873.15
Professional installation with seaming as required				
20. Tackless strip installation	48.33	LF	\$2.25	\$108.74
Perimeter installation per manufacturer specifications				
21. Baseboard installation	48.33	LF	\$8.75	\$422.89
Like kind and quality replacement with proper fastening				
22. Quarter round installation	48.33	LF	\$5.50	\$265.81
Finish trim installation with mitered corners				
23. Primer application	30.80	SF	\$1.25	\$38.50
High-quality primer for patch areas				
24. Wall paint application (2 coats)	386.67	SF	\$2.65	\$1,024.68
Premium latex paint with even coverage				

Generated on 2025-08-05 Page 2 of 6

# 25. Baseboard and quarter round paint

96.66 LF

\$2.25 \$217.48

Trim painting with cut-in technique

Bedroom 2 Subtotal: \$3,387.34

# Hallway

23.5 SF hallway space with standard reconstruction requirements. Height: 8 ft, wall area: 173.33 sq ft, floor area: 23.5 sq ft, perimeter: 21.67 lf.

D	O	- 4	-4!
Pre-	Con	stru	ction

Item	Qty	Unit	Unit Price	Total Price
26. Remove existing baseboard	21.67	LF	\$1.50	\$32.51
Careful removal to prevent wall damage				
27. Remove existing quarter round	21.67	LF	\$1.25	\$27.09
Trim removal with wall protection				

### Construction

Item	Qty	Unit	Unit Price	Total Price
28. Drywall patch and integration	17.60	SF	\$4.25	\$74.80
1/2" Type X gypsum board with feathered edges extending 6" beyond pate	ch area for s	eamless tra	nsition per IRC R702	
29. Carpet and pad installation	23.50	SF	\$6.50	\$152.75
Professional installation with seaming as required				
30. Tackless strip installation	21.67	LF	\$2.25	\$48.76
Perimeter installation per manufacturer specifications				
31. Baseboard installation	21.67	LF	\$8.75	\$189.61
Like kind and quality replacement with proper fastening				
32. Quarter round installation	21.67	LF	\$5.50	\$119.19
Finish trim installation with mitered corners				
33. Primer application	17.60	SF	\$1.25	\$22.00
High-quality primer for patch areas				
34. Wall paint application (2 coats)	173.33	SF	\$2.65	\$459.32
Premium latex paint with even coverage				
35. Baseboard and quarter round paint	43.34	LF	\$2.25	\$97.52
Trim painting with cut-in technique				

Hallway Subtotal: \$1,223.54

# **Living Room**

200.43 SF room with wood panel substrate, textured ceiling, and multiple fixture detach/reset requirements. Height: 8 ft, wall area: 464 sq ft, floor area: 200.43 sq ft, perimeter: 58 lf, ceiling area: 200.43 sq ft.

Generated on 2025-08-05 Page 3 of 6

Item	Qty	Unit	Unit Price	Total Pric
36. Remove existing carpet	180.43	SF	\$0.85	\$153.3
Carpet and pad removal including disposal preparation				
37. Remove existing baseboard	58.00	LF	\$1.50	\$87.0
Careful removal to prevent wall damage				
38. Remove existing quarter round	58.00	LF	\$1.25	\$72.5
Trim removal with wall protection				
39. Detach/reset large curtain rod	1.00	EA	\$65.00	\$65.0
Heavy-duty curtain rod system removal and reinstallation				
40. Detach/reset TV mount	1.00	EA	\$125.00	\$125.0
Wall-mounted TV bracket removal and reinstallation				
41. Detach/reset light fixture	1.00	EA	\$85.00	\$85.0
Electrical fixture disconnection and reconnection				
Construction				
Item	Qty	Unit	Unit Price	Total Pric
42. Wood panel patch and integration	26.40	SF	\$7.50	\$198.0
Wood panel substrate preparation and patching required for like kin	nd and quality repla	cement, inc		
preparation for paint	ra arra quanty ropia		cluding seam connection	on and
	200.43		suding seam connections \$6.50	
43. Carpet and pad installation  Professional installation with seaming as required		SF		\$1,302.8
43. Carpet and pad installation  Professional installation with seaming as required	200.43	SF	\$6.50	\$1,302.8
<ul> <li>43. Carpet and pad installation Professional installation with seaming as required</li> <li>44. Tackless strip installation Perimeter installation per manufacturer specifications</li> </ul>	200.43	SF LF	\$6.50	\$1,302.8 \$130.5
<ul> <li>43. Carpet and pad installation Professional installation with seaming as required</li> <li>44. Tackless strip installation Perimeter installation per manufacturer specifications</li> </ul>	200.43	SF LF	\$6.50 \$2.25	\$1,302.8 \$130.5
<ul> <li>43. Carpet and pad installation  Professional installation with seaming as required</li> <li>44. Tackless strip installation  Perimeter installation per manufacturer specifications</li> <li>45. Baseboard installation  Like kind and quality replacement with proper fastening</li> </ul>	200.43	SF LF LF	\$6.50 \$2.25	\$1,302.8 \$130.5 \$507.5
<ul> <li>43. Carpet and pad installation</li></ul>	200.43 58.00 58.00	SF LF LF	\$6.50 \$2.25 \$8.75	\$1,302.8 \$130.5 \$507.5 \$319.0
<ul> <li>43. Carpet and pad installation  Professional installation with seaming as required</li> <li>44. Tackless strip installation  Perimeter installation per manufacturer specifications</li> <li>45. Baseboard installation  Like kind and quality replacement with proper fastening</li> <li>46. Quarter round installation</li> </ul>	200.43 58.00 58.00	SF LF LF	\$6.50 \$2.25 \$8.75	\$1,302.8 \$130.5 \$507.5
<ul> <li>43. Carpet and pad installation  Professional installation with seaming as required</li> <li>44. Tackless strip installation  Perimeter installation per manufacturer specifications</li> <li>45. Baseboard installation  Like kind and quality replacement with proper fastening</li> <li>46. Quarter round installation  Finish trim installation with mitered corners</li> </ul>	200.43 58.00 58.00	SF LF LF	\$6.50 \$2.25 \$8.75 \$5.50	\$1,302.8 \$130.8 \$507.8 \$319.0
<ul> <li>43. Carpet and pad installation  Professional installation with seaming as required</li> <li>44. Tackless strip installation  Perimeter installation per manufacturer specifications</li> <li>45. Baseboard installation  Like kind and quality replacement with proper fastening</li> <li>46. Quarter round installation  Finish trim installation with mitered corners</li> <li>47. Primer application</li> </ul>	200.43 58.00 58.00	SF LF LF SF	\$6.50 \$2.25 \$8.75 \$5.50	\$1,302.8 \$130.8 \$507.8 \$319.0
<ul> <li>43. Carpet and pad installation  Professional installation with seaming as required</li> <li>44. Tackless strip installation  Perimeter installation per manufacturer specifications</li> <li>45. Baseboard installation  Like kind and quality replacement with proper fastening</li> <li>46. Quarter round installation  Finish trim installation with mitered corners</li> <li>47. Primer application  High-quality primer for wall and ceiling patch areas</li> </ul>	200.43 58.00 58.00 58.00 226.83	SF LF LF SF	\$6.50 \$2.25 \$8.75 \$5.50 \$1.25	\$1,302.8 \$130.5 \$507.5 \$319.0 \$283.5
<ul> <li>43. Carpet and pad installation</li></ul>	200.43 58.00 58.00 58.00 226.83	SF  LF  LF  SF  SF	\$6.50 \$2.25 \$8.75 \$5.50 \$1.25	\$1,302.8 \$130.8 \$507.8 \$319.0 \$283.8
43. Carpet and pad installation  Professional installation with seaming as required  44. Tackless strip installation  Perimeter installation per manufacturer specifications  45. Baseboard installation  Like kind and quality replacement with proper fastening  46. Quarter round installation  Finish trim installation with mitered corners  47. Primer application  High-quality primer for wall and ceiling patch areas  48. Wall paint application (2 coats)	200.43 58.00 58.00 226.83 464.00 200.43	SF  LF  LF  SF  SF	\$6.50 \$2.25 \$8.75 \$5.50 \$1.25	\$1,302.8 \$130.5 \$507.5 \$319.0 \$283.5

Living Room Subtotal: \$5,441.13

Generated on 2025-08-05 Page 4 of 6

### **General Conditions & Project Management**

Site protection, contents manipulation, cleanup, and waste management for occupied property reconstruction. Project-wide tasks including protection, detach/reset coordination, cleaning, and debris disposal.

### **Project Common**

Protection and coordination requirements for entire 450.27 SF project area. Applicable to all rooms on 1st floor; occupied status requires comprehensive contents manipulation.

## **Pre-Construction**

Item	Qty	Unit	Unit Price	Total Price
51. General site protection and masking	450.27	SF	\$0.90	\$405.24
Plastic sheeting, masking materials, drop cloths, and dust containment	nt systems for oc	cupied prope	erty per OSHA 1926.2	1
52. Contents manipulation and protection	4.00	RM	\$200.00	\$800.00
Move and protect contents in 4 rooms to enable work in occupied prop	perty, including to	emporary sto	rage coordination	

#### **Post-Construction**

Item	Qty	Unit	Unit Price	Total Price
53. Daily construction cleanup	5.00	Days	\$75.00	\$375.00
Dust control, debris containment, and surface protection to maintain habitabi	lity during	reconstruction		
54. Final construction cleaning	450.27	SF	\$0.85	\$382.73
Post-work cleaning including HEPA vacuuming for EPA RRP compliance				
55. Construction debris removal and disposal	3.00	CY	\$85.00	\$255.00
10 cu yd dumpster rental for reconstruction-generated waste, including hauli	ng and lai	ndfill fees per Arlı	ington County gu	idelines
56. Loading and hauling labor	3.50	Hours	\$50.00	\$175.00
Manual labor for debris handling and site cleanup				

Project Common Subtotal: \$2,392.97

Subtotal: \$14,968.78

Overhead (12.0%): \$1,796.25

Profit (8.0%): \$1,197.50

VA Sales Tax: \$222.77

**Estimate Total: \$18,185.30** 

**Overhead & Profit:** Combined 20% rate (12% overhead, 8% profit) applied due to project complexity involving multiple trade coordination (flooring, drywall, painting, trim), occupied property requiring specialized contents manipulation, detailed finish work requiring skilled craftsmanship, and sequential dependencies across multiple rooms. Rate reflects standard DMV market practices for residential reconstruction and is within industry standards for complex occupied property work.

**Tax Calculation:** Virginia sales tax of 5.75% applied to materials only per Virginia construction tax regulations and Virginia Tax Code §58.1-609.5. Labor costs are exempt from sales tax for residential reconstruction projects. Sales tax calculated on

Generated on 2025-08-05 Page 5 of 6

estimated materials portion (\$3,874) of total project cost. Monthly cost fluctuations of approximately 5% have been factored into pricing as of August 2025 market conditions.

**Scope of Work:** This estimate covers interior reconstruction work only as specified, based on the provided scope for water damage repair following a residential loss. All work performed in accordance with IRC 2018, Arlington County building codes, and local building codes (IRC), assuming like kind and quality replacement per IRC R702 standards. Contents manipulation and coordination included for occupied property status.

Warranty: 1-year workmanship warranty on all installations and materials.

Validity: Estimate valid for 30 days from date due to material cost volatility.

**Insurance Compliance:** Pricing positioned at appropriate percentile for optimal insurance adjuster approval, with detailed justification for all line items. Actual costs may vary with unforeseen site conditions, delays, or material availability; excludes permits unless required for patches exceeding local building code thresholds.

Generated on 2025-08-05 Page 6 of 6