Estimate

Estimate number EST-202508-5709-MERGED

Estimate Date: 2025-08-05

JJL Contractor Inc.

6517 Creek Run Dr Centreville, Virginia 20121 571-365-5055 projjlinc@gmail.com

Estimate for

15709 Rothschild Ct Haymarket, VA 20169-6177

Comprehensive interior reconstruction project including drywall repair, complete interior painting, carpet replacement, and restoration services across 6 rooms. Project includes high ceiling work requiring specialized equipment, extensive fixture coordination, and comprehensive site protection for occupied residence. All work performed to current building codes and industry standards.

Interior Reconstruction

Room-by-room reconstruction work including Bedroom (combined main/subroom/bay), Living Room, Kitchen (combined main/bay), Entry/Foyer, Hallway, and Garage. All work performed to current IRC and Virginia building standards.

Bedroom

343.53 SF floor area, peaked/8' ceiling height. Combined main bedroom, subroom, and bay area with comprehensive flooring replacement.

Pre-Construction

Item	Qty	Unit	Unit Price	Total Price
1. Floor Protection	343.53	SF	\$0.75	\$257.65
Protective film installation and removal for occupied residence				
2. Detach & Reset Items	5.00	EA	\$85.00	\$425.00
0.4:7:4.4.4.6.6.6.6.6.6.6.6.6.6.6.6.6.6.6.6.6		,	(4 = 4)	

Curtain/window drapery hardware (3 EA), recessed light fixture trim (1 EA), cold air return cover (1 EA)

Construction

Item	Qty	Unit	Unit Price	Total Price
3. Drywall Repair & Integration	192.00	SF	\$4.95	\$950.40
1/2" drywall installation on walls (96 SF) and ceiling (96 SF), taping, floati	ng, and textu	ıre matching		
4. Primer Application	192.00	SF	\$1.45	\$278.40
High-quality primer application on all new and repaired drywall surfaces				
5. Wall Painting	758.35	SF	\$2.70	\$2,047.55
Two-coat premium paint application on all walls				
6. Ceiling Painting	365.26	SF	\$2.70	\$986.20
Two-coat premium paint application on ceiling				
7. Carpet Removal	343.53	SF	\$1.55	\$532.47
Complete removal of existing carpet and padding				
8. Carpet Installation	371.00	SF	\$5.15	\$1,910.65
	0 17	1 00/	(5 ()	

New carpet installation with premium padding and professional stretch-in method (includes 8% waste factor)

Bedroom Subtotal: \$7,388.32

Living Room

541.93 SF floor area, 18'3" high ceiling requiring specialized scaffolding equipment and safety protocols per OSHA 1926.451

Generated on 2025-08-05 Page 1 of 5

Item	Qty	Unit	Unit Price	Total Price
9. Floor Protection	541.93	SF	\$0.75	\$406.45
Protective film installation and removal for occupied residence				
10. Large Fixture Protection	2.00	EA	\$45.00	\$90.00
Mask and cover large ornate light fixtures during construction				
11. Detach & Reset Items	2.00	EA	\$85.00	\$170.00
Large curtain and window drapery hardware for 2-story height				
Construction				
Item	Qty	Unit	Unit Price	Total Price
12. Drywall Repair & Integration	32.00	SF	\$4.95	\$158.40
1/2" drywall installation on ceiling (32 SF), taping, floating, and text	ture matching			
13. Primer Application	32.00	SF	\$1.45	\$46.40
High-quality primer application on all new and repaired drywall sur	faces			
14. High Wall Painting	1,659.00	SF	\$3.85	\$6,387.15
Specialized wall painting for 18'3" height using professional scaffol	lding and safety equ	iipment		
15. High Ceiling Painting	541.93	SF	\$3.85	\$2,086.43
Specialized ceiling painting for 18'3" height using professional scale	ffolding and safety e	equipment		
40 11 11 12 12 13 13 13	541.93	SF	\$0.75	\$406.45
16. Height Premium Labor				

Kitchen

289.74 SF floor area, 8' ceiling height. Combined main kitchen and bay area with careful attention to fixture protection.

Dro	Cana	4	ction
Pre-	Cons	STruc	noite

Item	Qty	Unit	Unit Price	Total Price
17. Floor Protection	289.74	SF	\$0.75	\$217.31
Protective film installation and removal for occupied residence				
18. Large Fixture Protection	1.00	EA	\$45.00	\$45.00
Mask and cover large light fixture during construction				
19. Detach & Reset Items	7.00	EA	\$85.00	\$595.00
Recessed light trim (6 EA) and window drapery hardware (1 EA)				

Construction

Item	Qty	Unit	Unit Price	Total Price	
20. Drywall Repair & Integration	24.00	SF	\$4.95	\$118.80	

1/2" drywall installation on walls (12 SF) and ceiling (12 SF), taping, floating, and texture matching

Generated on 2025-08-05 Page 2 of 5

21. Primer Application	24.00	SF	\$1.45	\$34.80
High-quality primer application on all new and repaired drywall surfaces				
22. Wall Painting	451.31	SF	\$2.70	\$1,218.54
Two-coat premium paint application on walls				
23. Ceiling Painting	289.74	SF	\$2.70	\$782.30
Two-coat premium paint application on ceiling				

Kitchen Subtotal: \$3,011.74

Entry/Foyer

99.83 SF floor area, 18'3" high ceiling requiring specialized scaffolding equipment and safety protocols per OSHA 1926.451

-	_		4.0	
Pre-	COI	nstri	JCI	on

Item	Qty	Unit	Unit Price	Total Price
24. Floor Protection	99.83	SF	\$0.75	\$74.87
Protective film installation and removal for occupied residence				
25. Large Fixture Protection	1.00	EA	\$45.00	\$45.00
Mask and cover large ornate light fixture during construction				

Construction

Item	Qty	Unit	Unit Price	Total Price	
26. High Wall Painting	610.88	SF	\$3.85	\$2,351.89	
Specialized wall painting for 18'3" height using professional scaffolding at	nd safety equ	iipment			
27. High Ceiling Painting	99.83	SF	\$3.85	\$384.35	
Specialized ceiling painting for 18'3" height using professional scaffolding	and safety e	equipment			
28. Height Premium Labor	99.83	SF	\$0.75	\$74.87	
Additional labor costs for elevated work and safety measures					

Entry/Foyer Subtotal: \$2,930.98

Hallway

431.33 SF floor area, 8' ceiling height with extensive fixture coordination requirements

_	_		4.0
Pre-	Cons	stru	ction

Item	Qty	Unit	Unit Price	Total Price
29. Floor Protection	431.33	SF	\$0.75	\$323.50
Protective film installation and removal for occupied residence				
30. Large Fixture Protection	1.00	EA	\$45.00	\$45.00
Mask and cover large ornate light fixture during construction				
31. Detach & Reset Items	15.00	EA	\$85.00	\$1,275.00

Recessed light fixture trim (6 EA), Heat/AC registers (4 EA), cold air return covers (2 EA), smoke detectors (2 EA), curtain/window hardware (1 EA)

Generated on 2025-08-05 Page 3 of 5

Construction				
Item	Qty	Unit	Unit Price	Total Price
32. Wall Painting	641.86	SF	\$2.70	\$1,733.02
Two-coat premium paint application on walls				
33. Ceiling Painting	431.33	SF	\$2.70	\$1,164.59
Two-coat premium paint application on ceiling				

Hallway Subtotal: \$4,541.11

Garage

429.02 SF floor area, 8' ceiling height. 2-car garage with special attention to garage door hardware and opener units.

Pre-Construction

Item	Qty	Unit	Unit Price	Total Price
34. Floor Protection	429.02	SF	\$0.75	\$321.76

Protective film installation and removal for occupied residence

Construction

Item	Qty	Unit	Unit Price	Total Price
35. Drywall Repair & Integration	48.00	SF	\$4.95	\$237.60
1/2" drywall installation on ceiling (48 SF), taping, floating, and texture matc	hing			
36. Primer Application	48.00	SF	\$1.45	\$69.60
High-quality primer application on all new and repaired drywall surfaces				
37. Wall Painting	576.00	SF	\$2.70	\$1,555.20
Two-coat premium paint application on walls, careful work around garage door supports				
38. Ceiling Painting	429.02	SF	\$2.70	\$1,158.35
Two-coat premium paint application on ceiling				

Garage Subtotal: \$3,342.52

Project Management & Site Services

Comprehensive project coordination, protection services, and cleanup management for occupied residence

Project Common Items

Project-wide services including coordination, protection, cleanup, and debris management

Pre-Construction

Item	Qty Unit	Unit Price	Total Price
39. Material Delivery Coordination	1.00 LS	\$150.00	\$150.00

Scheduled delivery management to minimize disruption in occupied home

Generated on 2025-08-05 Page 4 of 5

40. Daily Construction Cleanup

12.00 DAY

\$20.00

\$240.00

Ongoing site maintenance and safety protocols for occupied residence including dust control per OSHA 1910.1000

41. Scaffold Rental & Setup

1.00 LS

\$275.00

\$275.00

Professional scaffolding rental and setup for high-ceiling work (18'3") compliant with OSHA 1926.451 standards

Post-Construction

Item	Qty	Unit	Unit Price	Total Price
42. Construction Debris Disposal	1.00	LS	\$870.00	\$870.00
Professional waste management including 10-yard dumpster ren for 4.5 cubic yards total waste	tal, material segregat	ion, and pr	roper disposal at author	ized facilities
43. Professional Carpet Cleaning	431.33	SF	\$0.50	\$215.66
Professional deep cleaning and deodorizing service for hallway of	carpet as specified for	odor conti	rol	
44. Final Construction Cleaning	1.00	LS	\$355.00	\$355.00
Comprehensive post-construction cleaning including detailed dus	st removal, surface pr	eparation,	and final quality prepara	ation

Project Common Items Subtotal: \$2,105.67

Subtotal: \$33,071.62

Overhead (17.0%): \$5,622.18

VA Sales Tax: \$457.43

Estimate Total: \$39,151.23

Overhead & Profit: 17% applied to cover project management, supervision, quality control, and coordination of multiple trades including drywall, painting, flooring, and fixture work. **Sales Tax:** Virginia rate of 6.0% applied to materials only; labor is tax-exempt for residential construction per Virginia state tax code.

Scope of Work: This estimate covers comprehensive interior reconstruction including drywall repair, interior painting, carpet replacement, and all associated restoration services. All materials will meet "like kind and quality" standards. **Warranty:** 2-year workmanship warranty on all installation and repair work. **Timeline:** Project estimated at 12-18 business days depending on material delivery and drying times. **Terms:** Estimate valid for 30 days. Additional work beyond this scope will require separate pricing. Payment terms available upon contract execution.

Generated on 2025-08-05 Page 5 of 5