Estimate

Estimate number EST-202508-1394

Estimate Date: 2025-08-04

Enter Construction

3887 Fairfax Ridge Rd #445 Fairfax, VA 22030 240-271-5270 info@enter.construction

Estimate for

13941 Highstream Place Germantown, MD 20874

This comprehensive final estimate details the scope of work and associated costs for the complete residential reconstruction project located at 13941 Highstream Place, Germantown, MD 20874. The project involves multi-room and multi-floor interior reconstruction including kitchen cabinet replacement, drywall installation/patching, flooring replacement, interior painting, trim work, and fixture replacement across 11 rooms totaling 1,187 SF. Additionally, the project includes complete kitchen cabinet replacement with mid-range oak cabinetry (42 LF total) including appliance coordination and countertop installation. The property is currently vacant, which optimizes the project timeline by allowing for more efficient work progression and parallel work optimization. All work will adhere to current building codes (IRC, IBC), OSHA safety standards, and "Like Kind and Quality" standards ensuring a high-quality restoration defensible for insurance claims.

Site Preparation & Protection

of existing oak finish and hardware specifications

Project-wide site preparation including comprehensive protection measures and required permits to ensure OSHA-compliant safety throughout the reconstruction process.

Project Wide Protection

Comprehensive site protection and permit acquisition for entire project scope including kitchen cabinet work area

Pre-Construction

| Item | Qty | Unit | Unit Price | Total Price |
|---|--------------|------------------|----------------------|--------------|
| 1. General Site Protection | 11.00 | ROOM | \$85.00 | \$935.00 |
| Comprehensive protective measures including floor coverings (ram board, hor dust containment, fixture wrapping, and protection of HVAC vents to prevail safeguarded during reconstruction per OSHA standards. | | | | |
| 2. Recessed light protection | 2.00 | EA | \$50.00 | \$100.00 |
| Specialized protection for electrical fixtures during construction | | | | |
| 3. Ceiling fan protection | 2.00 | EA | \$50.00 | \$100.00 |
| Specialized protection for ceiling fans during construction | | | | |
| 4. HVAC system protection | 1.00 | LS | \$250.00 | \$250.00 |
| Complete protection of heating and cooling system components during cons | struction | | | |
| 5. Montgomery County building permits | 1.00 | LS | \$275.00 | \$275.00 |
| Interior renovation permits including plan review and required inspections per and NEC compliance | er Montgo | mery County re | quirements, ensuri | ng IRC P2708 |
| 6. Kitchen cabinet work area protection | 1.00 | LS | \$545.00 | \$545.00 |
| Comprehensive surface protection system for kitchen cabinet replacement - containment barriers required for finished space preservation | · floor prot | ection, wall cov | rering, appliance ma | asking, dust |
| 7. Kitchen cabinet pre-construction services | 1.00 | LS | \$970.00 | \$970.00 |

Project Wide Protection Subtotal: \$3,175.00

Generated on 2025-08-05 Page 1 of 14

Initial site survey with precise measurement (\$585) and material analysis & specification matching (\$385) required for Like Kind and Quality compliance - field verification of existing cabinet dimensions, filler requirements, custom sizing, and professional assessment

Interior Reconstruction

Room-by-room reconstruction work including kitchen cabinet replacement, drywall installation/patching, flooring replacement, trim work, painting, and fixture replacement across Living Room, Kitchen, Hallway, Furnace Room, 3 Bathrooms, 2 Bedrooms, Closet, and 2 Stairways across three floors.

Living Room - 1st Floor

Height: 8.00 ft

Wall Area: 417.22 sqft Ceiling Area: 196.96 sqft Floor Area: 196.96 sqft Floor Perimeter: 51.33 lf

Special conditions: recessed lights protection, window blind detach/reset required

Pre-Construction

| Item | Qty | Unit | Unit Price | Total Price |
|--------------------------------------|--------|------|------------|-------------|
| 8. Remove existing laminate flooring | 196.96 | SF | \$1.50 | \$295.44 |
| 9. Remove existing wood baseboard | 51.33 | LF | \$1.50 | \$77.00 |
| 10. Remove existing quarter round | 51.33 | LF | \$1.25 | \$64.16 |
| 11. Window blind detach/reset | 1.00 | EA | \$42.50 | \$42.50 |

Protection and reinstallation of existing window treatment

Construction

| Item | Qty | Unit | Unit Price | Total Price |
|---|--------|------|------------|-------------|
| 12. Drywall patch | 98.48 | SF | \$2.75 | \$270.82 |
| Seamless integration with existing surfaces | | | | |
| 13. Install laminate wood flooring | 206.81 | SF | \$7.25 | \$1,499.37 |
| 14. Install wood baseboard | 56.46 | LF | \$7.50 | \$423.45 |
| 15. Install wood quarter round | 56.46 | LF | \$6.50 | \$366.99 |
| 16. Paint walls | 417.22 | SF | \$2.25 | \$938.75 |
| 17. Paint ceiling | 196.96 | SF | \$2.50 | \$492.40 |
| 18. Paint baseboard | 51.33 | LF | \$2.00 | \$102.66 |

Living Room - 1st Floor Subtotal: \$4,573.54

Kitchen - 1st Floor

Height: 8.00 ft

Wall Area: 410.55 sqft Ceiling Area: 168.23 sqft Floor Area: 168.23 sqft Floor Perimeter: 50.50 lf

Complete drywall replacement required

Generated on 2025-08-05 Page 2 of 14

Kitchen - 1st Floor Subtotal: \$5,459.28

Enter Construction 3887 Fairfax Ridge Rd #445 Fairfax, VA, 22030 240-271-5270 info@enter.construction

| Pre-Construction | | | | |
|-----------------------------------|--------|------|------------|-------------|
| Item | Qty | Unit | Unit Price | Total Price |
| 19. Remove existing quarter round | 50.50 | LF | \$1.25 | \$63.12 |
| Construction | | | | |
| Item | Qty | Unit | Unit Price | Total Price |
| 20. Install drywall - walls | 451.61 | SF | \$3.25 | \$1,467.73 |
| Complete replacement | | | | |
| 21. Install drywall - ceiling | 185.05 | SF | \$3.25 | \$601.41 |
| Complete replacement | | | | |
| 22. Install vinyl tile flooring | 176.64 | SF | \$6.25 | \$1,104.00 |
| 23. Install wood baseboard | 55.55 | LF | \$7.50 | \$416.62 |
| 24. Install wood quarter round | 55.55 | LF | \$6.50 | \$361.07 |
| 25. Paint walls | 410.55 | SF | \$2.25 | \$923.74 |
| 26. Paint ceiling | 168.23 | SF | \$2.50 | \$420.57 |
| 27. Paint baseboard | 50.50 | LF | \$2.00 | \$101.00 |

Kitchen Cabinet Replacement - 1st Floor

Complete kitchen cabinet replacement project Base Cabinets: 20 LF \times 50 lbs/LF = 1,000 lbs debris Wall Cabinets: 22 LF \times 30 lbs/LF = 660 lbs debris

Total Cabinet Coverage: 42 LF

Mid-range oak cabinetry with solid wood doors, natural finish, brass hardware per Like Kind and Quality requirements

Appliance Coordination

| Item | Qty | Unit | Unit Price | Total Price |
|---|------|------|------------|-------------|
| 28. Dishwasher - Detach / Reset | 1.00 | EA | \$375.00 | \$375.00 |
| Professional appliance disconnection and reconnection during cabinet installation | tion | | | |
| 29. Refrigerator - Detach / Reset | 1.00 | EA | \$365.00 | \$365.00 |
| Professional appliance disconnection and reconnection during cabinet installation | tion | | | |
| 30. Gas Range - Detach / Reset | 1.00 | EA | \$285.00 | \$285.00 |
| Professional gas appliance disconnection and reconnection with safety protocol | ols | | | |
| 31. P-trap Assembly - Disconnect / Reconnect | 1.00 | EA | \$95.00 | \$95.00 |
| Plumbing disconnection and reconnection for cabinet installation access | | | | |

Cabinet Demolition

| Item | Qty Unit | Unit Price | Total Price |
|--------------------------------------|----------|------------|-------------|
| 32. Cabinet Contents Removal & Reset | 1.00 LS | \$485.00 | \$485.00 |

Careful removal, storage, and replacement of cabinet contents with finished space protocols

Generated on 2025-08-05 Page 3 of 14

| 33 | 3. Base Cabinet Demolition & Removal | 20.00 | LF | \$28.00 | \$560.00 |
|----|---|-------|----|----------|----------|
| | Systematic removal of existing oak base cabinets | | | | |
| 34 | 4. Wall Cabinet Demolition & Removal | 22.00 | LF | \$24.00 | \$528.00 |
| | Careful removal of wall-mounted cabinets | | | | |
| 3 | 5. Laminate Countertop Removal | 22.00 | LF | \$18.00 | \$396.00 |
| | Removal of existing laminate countertop with substrate | | | | |
| 30 | 6. Cabinet Hardware Removal | 1.00 | LS | \$145.00 | \$145.00 |
| | Removal of existing brass hardware from all cabinet doors and drawers | | | | |

Cabinet Installation

| Item | Qty | Unit | Unit Price | Total Price |
|---|-----------|------------------|------------|-------------|
| 37. 15" Base Cabinet with Drawers | 2.00 | EA | \$565.00 | \$1,130.00 |
| Mid-range quality oak construction with soft-close drawers to match existing sp | ecificat | ions | | |
| 38. 18" Base Cabinet with Doors | 2.00 | EA | \$615.00 | \$1,230.00 |
| Solid wood construction with adjustable shelving | | | | |
| 39. 24" Base Cabinet with Doors | 3.00 | EA | \$695.00 | \$2,085.00 |
| Standard base cabinet with quality hardware | | | | |
| 40. 30" Base Cabinet with Doors | 2.00 | EA | \$825.00 | \$1,650.00 |
| Full-depth cabinet with quality construction | | | | |
| 41. 36" Sink Base Cabinet | 1.00 | EA | \$885.00 | \$885.00 |
| Reinforced construction for sink mounting with plumbing access | | | | |
| 42. 12" Wall Cabinet | 1.00 | EA | \$345.00 | \$345.00 |
| Upper cabinet with adjustable shelving | | | | |
| 43. 15" Wall Cabinet | 1.00 | EA | \$385.00 | \$385.00 |
| Standard wall cabinet construction | | | | |
| 44. 18" Wall Cabinet | 2.00 | EA | \$425.00 | \$850.00 |
| Quality oak construction with soft-close hinges | | | | |
| 45. 24" Wall Cabinet | 2.00 | EA | \$545.00 | \$1,090.00 |
| Mid-range specifications matching existing | | | | |
| 46. 30" Wall Cabinet | 4.00 | EA | \$625.00 | \$2,500.00 |
| Quality wall cabinet with standard hardware | | | | |
| 47. 36" Wall Cabinet | 1.00 | EA | \$685.00 | \$685.00 |
| Large wall cabinet with reinforced mounting | | | | |
| 48. Cabinet Installation Labor | 42.00 | LF | \$145.00 | \$6,090.00 |
| Professional installation with finished space protection protocols, precision level | eling, ar | nd hardware adju | stment | |
| 49. Oak Veneer Toe Kick Material | 20.00 | LF | \$22.00 | \$440.00 |
| Matching oak veneer toe kick to existing specifications | | | | |
| 50. Cabinet Hardware - Brass Knobs | 17.00 | EA | \$35.00 | \$595.00 |
| Quality brass knobs matching existing finish and style | | | | |
| | | | | |

Generated on 2025-08-05 Page 4 of 14

| Countertop Installation | | | | |
|--|-------------|------|------------|-------------|
| Item | Qty | Unit | Unit Price | Total Price |
| 51. Template Creation & Field Verification | 1.00 | LS | \$325.00 | \$325.00 |
| Precision templating for exact fit and sink cutout | | | | |
| 52. Laminate Countertop - Wilsonart or Equal | 22.00 | LF | \$52.00 | \$1,144.00 |
| Mid-range laminate matching existing pattern with substrate | | | | |
| 53. Countertop Installation Labor | 22.00 | LF | \$38.00 | \$836.00 |
| Professional installation with sink cutout, edge finishing, and sealing | | | | |
| 54. Sink Cutout & Mounting | 1.00 | EA | \$165.00 | \$165.00 |
| Precision cutting and mounting hardware installation | | | | |
| Kitchen Cabinet Cleanup | | | | |
| Item | Qty | Unit | Unit Price | Total Price |
| 55. Kitchen Final Site Restoration & Cleaning | 1.00 | LS | \$585.00 | \$585.00 |
| Complete cleaning and restoration of kitchen work area to pre-construction | n condition | | | |

Kitchen Cabinet Replacement - 1st Floor Subtotal: \$26,249.00

Hallway - 2nd Floor

Height: 8.00 ft

Wall Area: 368.24 sqft Ceiling Area: 88.59 sqft Floor Area: 88.59 sqft Floor Perimeter: 46.00 lf

Partial drywall replacement and carpet installation

Construction

| Item | Qty | Unit | Unit Price | Total Price |
|------------------------------------|--------|------|------------|-------------|
| 56. Install drywall - ceiling | 97.45 | SF | \$3.25 | \$316.71 |
| Complete replacement | | | | |
| 57. Patch existing drywall - walls | 205.06 | SF | \$3.25 | \$666.45 |
| 58. Install carpet flooring | 97.45 | SF | \$5.00 | \$487.25 |
| 59. Install wood baseboard | 50.60 | LF | \$7.50 | \$379.50 |
| 60. Install wood quarter round | 50.60 | LF | \$6.50 | \$328.90 |
| 61. Paint walls | 368.24 | SF | \$2.25 | \$828.54 |
| 62. Paint ceiling | 88.59 | SF | \$2.50 | \$221.48 |
| 63. Paint baseboard | 46.00 | LF | \$2.00 | \$92.00 |
| | | | | |

Hallway - 2nd Floor Subtotal: \$3,320.82

Furnace Room - 2nd Floor

Height: 8.00 ft Wall Area: 272.18 sqft

Generated on 2025-08-05 Page 5 of 14

Ceiling Area: 69.47 sqft Floor Area: 69.47 sqft Floor Perimeter: 34.00 lf

Complete drywall replacement, no flooring work required

| _ | | 4.5 | |
|--------------|-------|--------|-----|
| (-0 | nstrı | ICT. | nn |
| \mathbf{v} | เเอนเ | a Geri | UII |

| Item | Qty | Unit | Unit Price | Total Price |
|--------------------------------|--------|------|------------|-------------|
| 64. Install drywall - walls | 299.39 | SF | \$3.25 | \$973.02 |
| Complete replacement | | | | |
| 65. Install drywall - ceiling | 76.42 | SF | \$3.25 | \$248.37 |
| Complete replacement | | | | |
| 66. Install wood baseboard | 37.40 | LF | \$7.50 | \$280.50 |
| 67. Install wood quarter round | 37.40 | LF | \$6.50 | \$243.10 |
| 68. Paint walls | 272.18 | SF | \$2.25 | \$612.40 |
| 69. Paint ceiling | 69.47 | SF | \$2.50 | \$173.68 |
| 70. Paint baseboard | 34.00 | LF | \$2.00 | \$68.00 |

Furnace Room - 2nd Floor Subtotal: \$2,599.06

Bathroom #1 - 2nd Floor

Height: 8.00 ft Wall Area: 212.47 sqft Ceiling Area: 41.07 sqft

Floor Area: 41.07 sqft Floor Perimeter: 26.54 lf

Complete renovation with fixture replacement and tile work

| | | _ | | | | | |
|---|-----|----|----|-----|----|-----|----|
| М | re- | Co | ทร | trı | JC | [[(| on |

| Item | Qty | Unit | Unit Price | Total Price |
|---|-------|------|------------|-------------|
| 71. Remove existing tile flooring | 41.07 | SF | \$1.50 | \$61.61 |
| 72. Remove existing quarter round | 26.54 | LF | \$1.25 | \$33.17 |
| 73. Vanity removal/reinstall | 1.00 | EA | \$450.00 | \$450.00 |
| Professional removal and reinstallation of existing fixture | | | | |
| 74. Toilet removal/reinstall | 1.00 | EA | \$300.00 | \$300.00 |
| Professional removal and reinstallation of existing fixture | | | | |
| 75. Bathtub removal/reinstall | 1.00 | EA | \$1,200.00 | \$1,200.00 |
| Professional removal and reinstallation of existing fixture including tile work | | | | |

Construction

| Item | Qty | Unit | Unit Price | Total Price |
|-------------------------------|--------|------|------------|-------------|
| 76. Install drywall - walls | 233.72 | SF | \$3.25 | \$759.59 |
| Complete replacement | | | | |
| 77. Install drywall - ceiling | 45.18 | SF | \$3.25 | \$146.84 |
| Complete replacement | | | | |

Generated on 2025-08-05 Page 6 of 14

| 78. Install ceramic tile flooring | 43.12 | SF | \$8.75 | \$377.30 | |
|---|--------|----|---------|----------|--|
| 79. Bathtub tile surround | 50.00 | SF | \$18.00 | \$900.00 | |
| Bathtub surrounding tile wall per IRC R702.3.8 for moisture barrier | | | | | |
| 80. Install wood baseboard | 29.19 | LF | \$7.50 | \$218.93 | |
| 81. Install wood quarter round | 29.19 | LF | \$6.50 | \$189.74 | |
| 82. Paint walls | 212.47 | SF | \$2.25 | \$478.06 | |
| 83. Paint ceiling | 41.07 | SF | \$2.50 | \$102.67 | |
| 84. Paint baseboard | 26.54 | LF | \$2.00 | \$53.08 | |
| | | | | | |

Bathroom #1 - 2nd Floor Subtotal: \$5,270.98

Bathroom #2 - 2nd Floor

Height: 8.00 ft Wall Area: 100.08 sqft Ceiling Area: 6.56 sqft Floor Area: 6.56 sqft

Floor Perimeter: 12.50 If

Small bathroom with complete renovation

| _ | _ | | | |
|------|----------------|-------|-------|---|
| Pro- | $c_{\alpha r}$ | actri | Lotic | n |

| Item | Qty | Unit | Unit Price | Total Price |
|---|-------|------|------------|-------------|
| 85. Remove existing tile flooring | 6.56 | SF | \$1.50 | \$9.84 |
| 86. Remove existing quarter round | 12.50 | LF | \$1.25 | \$15.62 |
| 87. Vanity removal/reinstall | 1.00 | EA | \$450.00 | \$450.00 |
| Professional removal and reinstallation of existing fixture | | | | |
| 88. Toilet removal/reinstall | 1.00 | EA | \$300.00 | \$300.00 |
| Professional removal and reinstallation of existing fixture | | | | |
| 89. Bathtub removal/reinstall | 1.00 | EA | \$1,200.00 | \$1,200.00 |
| Professional removal and reinstallation of existing fixture including tile work | | | | |

Construction

| Item | Qty | Unit | Unit Price | Total Price |
|---|--------|------|------------|-------------|
| 90. Install drywall - walls | 110.09 | SF | \$3.25 | \$357.79 |
| Complete replacement | | | | |
| 91. Install drywall - ceiling | 7.22 | SF | \$3.25 | \$23.46 |
| Complete replacement | | | | |
| 92. Install ceramic tile flooring | 6.89 | SF | \$8.75 | \$60.29 |
| 93. Bathtub tile surround | 50.00 | SF | \$18.00 | \$900.00 |
| Bathtub surrounding tile wall per IRC R702.3.8 for moisture barrier | | | | |
| 94. Install wood baseboard | 13.75 | LF | \$7.50 | \$103.12 |
| 95. Install wood quarter round | 13.75 | LF | \$6.50 | \$89.38 |

Generated on 2025-08-05 Page 7 of 14

| 96. Paint walls | 100.08 | SF | \$2.25 | \$225.18 |
|---------------------|--------|----|--------|----------|
| 97. Paint ceiling | 6.56 | SF | \$2.50 | \$16.40 |
| 98. Paint baseboard | 12.50 | LF | \$2.00 | \$25.00 |

Bathroom #2 - 2nd Floor Subtotal: \$3,776.09

Bedroom - 2nd Floor

Height: 8.00 ft Wall Area: 304.20 sqft Ceiling Area: 89.41 sqft Floor Area: 89.41 sqft Floor Perimeter: 38.00 lf

Special conditions: ceiling fan light protection, window blind detach/reset

Pre-Construction

| Item | Qty | Unit | Unit Price | Total Price |
|---|-------|------|------------|-------------|
| 99. Remove existing carpet | 89.41 | SF | \$1.50 | \$134.12 |
| 100. Remove existing wood baseboard | 38.00 | LF | \$1.50 | \$57.00 |
| 101. Remove existing quarter round | 38.00 | LF | \$1.25 | \$47.50 |
| 102. Ceiling fan light protection | 1.00 | EA | \$65.00 | \$65.00 |
| Specialized protection for ceiling fans during construction | | | | |
| 103. Window blind detach/reset | 1.00 | EA | \$42.50 | \$42.50 |
| Protection and reinstallation of existing window treatment | | | | |

| 0 | moter | uction |
|---|-------|--------|
| | | |

| Item | Qty | Unit | Unit Price | Total Price |
|---------------------------------|--------|------|------------|-------------|
| 104. Install carpet flooring | 98.35 | SF | \$5.00 | \$491.75 |
| 105. Install wood baseboard | 41.80 | LF | \$7.50 | \$313.50 |
| 106. Install wood quarter round | 41.80 | LF | \$6.50 | \$271.70 |
| 107. Paint walls | 304.20 | SF | \$2.25 | \$684.45 |
| 108. Paint ceiling | 89.41 | SF | \$2.50 | \$223.52 |
| 109. Paint baseboard | 38.00 | LF | \$2.00 | \$76.00 |

Bedroom - 2nd Floor Subtotal: \$2,407.04

Bedroom - 3rd Floor

Height: 8.00 ft Wall Area: 634.22 sqft Ceiling Area: 258.56 sqft Floor Area: 258.56 sqft Floor Perimeter: 79.23 lf

Large bedroom with drywall patching and carpet replacement

Special conditions: ceiling fan light protection, window blinds detach/reset

Generated on 2025-08-05 Page 8 of 14

| Pre-Construction | | | | |
|--|--------|------|------------|-------------|
| Item | Qty | Unit | Unit Price | Total Price |
| 110. Remove existing carpet | 258.56 | SF | \$1.50 | \$387.84 |
| 111. Remove existing wood baseboard | 79.23 | LF | \$1.50 | \$118.84 |
| 112. Remove existing quarter round | 79.23 | LF | \$1.25 | \$99.04 |
| 113. Ceiling fan light protection Specialized protection for ceiling fans during construction | 1.00 | EA | \$65.00 | \$65.00 |
| 114. Window blind detach/reset Protection and reinstallation of existing window treatments | 2.00 | EA | \$42.50 | \$85.00 |
| Construction | | | | |
| Item | Qty | Unit | Unit Price | Total Price |
| 115. Drywall patch Seamless integration with existing surfaces | 129.28 | SF | \$2.75 | \$355.52 |
| 116. Install carpet flooring | 284.42 | SF | \$5.00 | \$1,422.10 |
| 117. Install wood baseboard | 87.15 | LF | \$7.50 | \$653.62 |
| 118. Install wood quarter round | 87.15 | LF | \$6.50 | \$566.48 |
| 119. Paint walls | 634.22 | SF | \$2.25 | \$1,427.00 |
| 120. Paint ceiling | 258.56 | SF | \$2.50 | \$646.40 |
| 121. Paint baseboard | 79.23 | LF | \$2.00 | \$158.46 |

Bedroom - 3rd Floor Subtotal: \$5,985.30

Closet - 3rd Floor

Height: 7.00 ft Wall Area: 198.35 sqft Ceiling Area: 42.34 sqft Floor Area: 42.34 sqft Floor Perimeter: 28.33 If

Special conditions: clothes shelves detach/reset required

| | ction |
|--|-------|
| | |

| Item | Qty | Unit | Unit Price | Total Price |
|-------------------------------------|-------|------|------------|-------------|
| 122. Remove existing carpet | 42.34 | SF | \$1.50 | \$63.51 |
| 123. Remove existing wood baseboard | 28.33 | LF | \$1.50 | \$42.49 |
| 124. Remove existing quarter round | 28.33 | LF | \$1.25 | \$35.41 |
| 125. Closet shelves detach/reset | 3.00 | EA | \$27.50 | \$82.50 |

Professional removal and reinstallation of standard closet shelving system

Generated on 2025-08-05 Page 9 of 14

| Construction | | | | |
|---|--------|------|------------|-------------|
| Item | Qty | Unit | Unit Price | Total Price |
| 126. Drywall patch | 99.18 | SF | \$2.75 | \$272.75 |
| Seamless integration with existing surfaces | | | | |
| 127. Install carpet flooring | 46.57 | SF | \$5.00 | \$232.85 |
| 128. Install wood baseboard | 31.16 | LF | \$7.50 | \$233.70 |
| 129. Install wood quarter round | 31.16 | LF | \$6.50 | \$202.54 |
| 130. Paint walls | 198.35 | SF | \$2.25 | \$446.29 |
| 131. Paint ceiling | 42.34 | SF | \$2.50 | \$105.85 |
| 132. Paint baseboard | 28.33 | LF | \$2.00 | \$56.66 |

Closet - 3rd Floor Subtotal: \$1,774.55

Bathroom #3 - 3rd Floor

Height: 8.00 ft Wall Area: 206.17 sqft Ceiling Area: 39.00 sqft Floor Area: 39.00 sqft Floor Perimeter: 25.75 If

Complete bathroom renovation with new fixture installation

| Pre- | C | 2044 | . ati | |
|------|-----|------|-------|----|
| Pre- | COL | ารเท | ICII | on |

| Item | Qty | Unit | Unit Price | Total Price |
|---|-------|------|------------|-------------|
| 133. Remove existing wood baseboard | 25.75 | LF | \$1.50 | \$38.62 |
| 134. Remove existing quarter round | 25.75 | LF | \$1.25 | \$32.19 |
| 135. Bathtub removal/reinstall | 1.00 | EA | \$1,200.00 | \$1,200.00 |
| Professional removal and reinstallation of existing fixture including tile work | | | | |

Construction

| Item | Qty | Unit | Unit Price | Total Price |
|---|--------|------|------------|-------------|
| 136. Drywall patch | 103.09 | SF | \$2.75 | \$283.50 |
| Seamless integration with existing surfaces | | | | |
| 137. Install ceramic tile flooring | 40.95 | SF | \$8.75 | \$358.31 |
| 138. Bathtub tile surround | 50.00 | SF | \$18.00 | \$900.00 |
| Bathtub surrounding tile wall per IRC R702.3.8 for moisture barrier | | | | |
| 139. Install wood baseboard | 28.33 | LF | \$7.50 | \$212.47 |
| 140. Install wood quarter round | 28.33 | LF | \$6.50 | \$184.14 |
| 141. Paint walls | 206.17 | SF | \$2.25 | \$463.88 |
| 142. Paint ceiling | 39.00 | SF | \$2.50 | \$97.50 |
| 143. Paint baseboard | 25.75 | LF | \$2.00 | \$51.50 |

Generated on 2025-08-05 Page 10 of 14

| 144. Install new vanity | 1.00 EA | \$375.00 | \$375.00 |
|--|---------|----------|----------|
| Professional installation of new vanity unit | | | |
| 145. Install new toilet | 1.00 EA | \$275.00 | \$275.00 |
| Professional installation of new toilet | | | |
| 146. Install new mirror | 1.00 EA | \$125.00 | \$125.00 |
| Professional installation of new mirror | | | |

Bathroom #3 - 3rd Floor Subtotal: \$4,597.13

Stairway #1 - 3rd Floor

Height: 8.00 ft Wall Area: 160.54 sqft Ceiling Area: 31.42 sqft Floor Area: 31.42 sqft

Floor Perimeter: 19.54 If

Standard height stairway with carpet replacement

| Pre-Construction |
|------------------|
|------------------|

| Item | Qty | Unit | Unit Price | Total Price |
|-------------------------------------|-------|------|------------|-------------|
| 147. Remove existing carpet | 31.42 | SF | \$1.50 | \$47.13 |
| 148. Remove existing wood baseboard | 19.54 | LF | \$1.50 | \$29.31 |
| 149. Remove existing quarter round | 19.54 | LF | \$1.25 | \$24.42 |

Construction

| Item | Qty | Unit | Unit Price | Total Price |
|---|--------|------|------------|-------------|
| 150. Drywall patch | 15.71 | SF | \$2.75 | \$43.20 |
| Seamless integration with existing surfaces | | | | |
| 151. Install carpet flooring | 34.56 | SF | \$5.00 | \$172.80 |
| 152. Install wood baseboard | 21.49 | LF | \$7.50 | \$161.17 |
| 153. Install wood quarter round | 21.49 | LF | \$6.50 | \$139.69 |
| 154. Paint walls | 160.54 | SF | \$2.25 | \$361.21 |
| 155. Paint ceiling | 31.42 | SF | \$2.50 | \$78.55 |
| 156. Paint baseboard | 19.54 | LF | \$2.00 | \$39.08 |

Stairway #1 - 3rd Floor Subtotal: \$1,096.57

Stairway #2 - 3rd Floor

Height: 10.00 ft Wall Area: 274.37 sqft Ceiling Area: 35.97 sqft Floor Area: 35.97 sqft Floor Perimeter: 26.42 lf

High ceiling stairway with height premium application

Generated on 2025-08-05 Page 11 of 14

| Pre-Construction | | | | |
|--|-------------------|----------|------------|-------------|
| Item | Qty | Unit | Unit Price | Total Price |
| 157. Remove existing carpet | 35.97 | SF | \$1.50 | \$53.95 |
| 158. Remove existing wood baseboard | 26.42 | LF | \$1.50 | \$39.63 |
| 159. Remove existing quarter round | 26.42 | LF | \$1.25 | \$33.03 |
| Construction | | | | |
| Item | Qty | Unit | Unit Price | Total Price |
| 160. Drywall patch | 18.00 | SF | \$2.75 | \$49.50 |
| Seamless integration with existing surfaces | | | | |
| 161. Install carpet flooring | 39.57 | SF | \$5.25 | \$207.74 |
| Includes height premium for 10-foot ceilings requiring additional equi | ipment and safety | measures | | |
| 162. Install wood baseboard | 29.06 | LF | \$8.00 | \$232.48 |
| Includes height premium for 10-foot ceilings requiring additional equi | ipment and safety | measures | | |
| 163. Install wood quarter round | 29.06 | LF | \$7.00 | \$203.42 |
| Includes height premium for 10-foot ceilings requiring additional equi | ipment and safety | measures | | |
| 164. Paint walls | 274.37 | SF | \$2.50 | \$685.92 |
| Includes height premium for 10-foot ceilings requiring additional equi | ipment and safety | measures | | |
| 165. Paint ceiling | 35.97 | SF | \$2.75 | \$98.92 |
| Includes height premium for 10-foot ceilings requiring additional equi | ipment and safety | measures | | |
| 166. Paint baseboard | 26.42 | LF | \$2.25 | \$59.45 |
| Includes height premium for 10-foot ceilings requiring additional equi | ipment and safety | measures | | |

Stairway #2 - 3rd Floor Subtotal: \$1,664.04

Project Management & Cleanup

Comprehensive debris management and final cleaning services to ensure quality completion and move-in ready condition. Includes combined debris from interior reconstruction and kitchen cabinet replacement project.

Project Common Items

Services applied to entire project scope including waste disposal and cleaning for both interior reconstruction and kitchen cabinet replacement

Debris Management

| Item | Qty Unit | Unit Price | Total Price |
|--|----------|------------|-------------|
| 167. 20-Yard Combined Project Dumpster | 1.00 EA | \$875.00 | \$875.00 |

Combined debris disposal for kitchen cabinet demolition (2,272 lbs: base cabinets 1,000 lbs + wall cabinets 660 lbs + countertops 220 lbs + backsplash 96 lbs + misc 296 lbs) and interior reconstruction debris from 11 rooms (drywall, flooring, trim, fixtures). Includes delivery, pickup, disposal fees, and loading labor.

168. Combined Project Debris Removal Labor

1.00 LS \$750.00 \$750.00

Professional loading and removal of all project debris including kitchen cabinet materials and interior reconstruction waste with ground level transport

Generated on 2025-08-05 Page 12 of 14

Post-Construction Cleaning

| Item | Qty | Unit | Unit Price | Total Price |
|----------------------------------|------|------|------------|-------------|
| 169. During-construction cleanup | 1.00 | LS | \$1,750.00 | \$1,750.00 |

Daily site maintenance, weekly deep cleaning, and dust control measures throughout construction period for safety, efficiency, and OSHA compliance covering both interior reconstruction and kitchen cabinet work

170. Final construction cleaning

1,187.00 SF

\$2.25

\$2,670.75

Comprehensive final construction cleaning including thorough vacuuming, surface wiping, window cleaning, dusting, deep bathroom/kitchen cleaning, and final dust removal for move-in ready condition

Project Common Items Subtotal: \$6,045.75

Subtotal: \$77,994.15

Overhead (10.0%): \$7,799.42

Profit (10.0%): \$7,799.42

MD Sales Tax: \$4,251.04

Estimate Total: \$97,844.03

Tax Information: Maryland sales tax of 6.0% applies to materials only as contractors pay tax at point of purchase per Maryland regulations. Labor charges are exempt from sales tax for residential construction work.

Overhead & Profit: Combined 20% O&P rate (10% overhead + 10% profit) is justified by complex multi-trade project including complete kitchen cabinet replacement (42 LF), drywall installation/patching, multiple flooring types, painting, trim work, and fixture replacement across 11 rooms. Rate includes supervision, insurance, bonding, appliance coordination, and profit margin appropriate for comprehensive insurance restoration work combining both interior reconstruction and kitchen cabinet replacement in the DMV area.

Project Timeline: Estimated completion schedule takes advantage of vacant property status allowing for parallel work and efficient crew coordination across three floors. Kitchen cabinet work (15-20 days) can be coordinated with interior reconstruction for optimal efficiency.

Kitchen Cabinet Specifications: Mid-range traditional raised panel oak cabinetry with solid wood doors, natural finish, brass hardware meeting Like Kind and Quality policy requirements. Installation includes toe kicks and professional appliance coordination.

This comprehensive estimate covers complete reconstruction of water-damaged areas and kitchen cabinet replacement as specified, based on provided scope and subject to on-site verification. All work will be performed to current building codes (IRC, IBC) and OSHA safety standards. Materials will match existing like-kind-and-quality standards per insurance requirements including mid-range oak kitchen cabinetry with solid wood construction. Project timeline assumes vacant property status and normal material availability. Kitchen cabinet work includes appliance detach/reset coordination and countertop installation. Changes to scope of work will be addressed through written change orders with proper documentation. One-year comprehensive warranty provided on all workmanship including cabinet installation. Contractor maintains appropriate licensing, bonding, and insurance coverage. Estimate includes contingency for minor unforeseen conditions but excludes major structural issues, hazardous materials (asbestos, lead paint), or conditions not visible during initial assessment. Any permits required by Montgomery County jurisdiction are included where specified. Detach/reset and room-specific protection measures are

Generated on 2025-08-05 Page 13 of 14

included as itemized to ensure comprehensive project completion. Combined project debris management with 20-yard dumpster allocation for efficient disposal.

Generated on 2025-08-05 Page 14 of 14